SCHEDULE - B

Name of the Work: Construction of RCC drain and culverts in Chikkamarana Halli Layout main road and cross roads in Ward No. 18

Indent No: 9973

Sl. No	Description of item	Unit	Qty	Rate (Rs)	
				In figures	In words
1	Earthwork excavation for foundation of buildings, Culverts, water supply, sanitary lines and electrical conduits either in pits or in trenches 1.5m and above in width, in ordinary soil not exceeding 1.5m. In depth including dressing the bottom and sides of pits and trenches, stacking the excavated soil clear from edges of excavation with lead upto 50m after breaking of clods complete as per specifications. P No.5 Ino 2.4 PWDSR - 2013-14	Cum	276.60	140.0	Rupees One Hundred Forty Only
2	Providing and laying in position plain cement concrete of mix M 7.5 with OPC cement @ 180 kgs using 40mm and down size graded granite metal CA @ 0.85 cum and FA @ 0.57 cum machine mixed, concrete laid in layers not exceeding 15 cms thick, well compacted, in foundation and plinth, including cost of all materials, labour, HOM machinery, curing complete as per specifications. Specification No.KBS 4. 1,4.2 P No. 12 I no 4.3 PWDSR - 2013-14	Cum	34.58	4200.0	Rupees Four Thousand Two Hundred Only
3	Providing and removing centering, shuttering, strutting, propping etc., and removal of form work for vertical surface such as walls at any thickness, including attached pilasters, buttresses, plinth and string courses cost of all materials, labour complete as per specifications. specification No. KBS 4.6.2 P No 17. I No 4.31 PWDSR - 2013-14	Sqm	596.00	265.0	Rupees Two Hundred Sixty Five Only
	Providing an laying in position reinforced cement concrete of nominal mix M 20 with OPC @ 320 kgs with 20mm and down size graded granite metal, CA @ 0.878 cum and FA @ 0.459 cum and super palstisizer @ 3 ltr confirming to is 9103-1999 reaffirmed - 2008 machine mixed, concrete laid in layers not exceeding 15 cms thick, vibraited for all works in foundation plinth and ground floor level for retaining walls, return walls, walls (any thickness) including attached plasters, columns, piers, abutments, pillars, posts, struts, butresses, string or lacing courses, parapets, coping, bed blocks, plain window cills, fillets etc., including cost of all materials, labour, HOM of machinery, curing, complete as per specifications. Specification No.KBS 4.1, 4.6 P No.13. I No 1.11 PWDSR - 2013-14	Cum	75.90	5300.0	Rupees Five Thousand Three Hundred Only
	roviding and fixing Pre cast solid concrete kerb stones made out of CC 1:2:4 d finished with CM 1:3 plastering and finishing cutting etc., complete. of size 0 x 200 x 400 mm P 24 I NO.5.29.1 PWDSR - 2013-14	Nos	300.00	297.0	Rupees Two Hundred Ninety Seven Only

Description of item	Unit	Qty	Rate (Rs)	
			In figures	In words
ding TMT steel reinforcement for R.C.C work including straightening, g, bending, hooking, placing in position, lapping and / or welding ever required, tying with bindig wire and anchoring to the adjining bers wherever necessary complete as per design (laps, hooks and age shall not be measured and paid) cost of materials, labour, HOM of hinery complete as per spedification No. KBS 4.6.3 Page No.19.I No.4.46 DSR - 2013-14	Qtl	45.00	6800.0	Rupees Six Thousand Eight Hundred Only
viding and laying position reinforced cement concrete covering slabs deout of mix 1:1.50:3 with 20mm and down size granite metal mixed icrete laid in layers not exceeding 15cms vibrated including cost of terials, labor curing providing and laying in position including transportation mplete as per specification. (SLAB THICKNESS OF 10CMS)	Sqm	162.00	1300.0	Rupees One Thousand Three Hundred Only
nveying the excavated earth by private vehicle including loading and loading charges up to 10 kms with all lead and lift.	Cum	276.60	90.0	Rupees Ninety Only
ainting two coats after filling the surface with synthetic enamel paint in pproved shades on new plasered concrete surfaces, with materials, labour ompete as per specifications. Specification No.KRBS 800.3 MORT & H pecification No.800. P.No. 195. I no 24.1 PWDSR - 2013-14	Sqm	40.50	45.0	Rupees Forty Five Only